

Attachment B

SANTA FE COUNTY ROMERO PARK WATERLINE BID TAB

ITEM NO.	ITEM DESCRIPTION:	UNIT:	QTY:	UNIT PRICE	BID AMOUNT
BASE BID GENERAL ITEMS					
1	MOBILIZATION/DEMOBILIZATION	LS	1		
2	TRAFFIC CONTROL PLAN & TRAFFIC CONTROL, CIP	LS	1		
3	CONSTRUCTION STAKING, CIP.	LS	1		
4	CONSTRUCTION SURVEY, CIP.	LS	1		
6	CONSTRUCTION PROJECT SIGN, CIP	LS	1		
7	RELOCATION OF EXISTING UTILITIES	ALLOW	1	\$ 5,000.00	\$ 5,000.00
8	LABORATORY TESTING ALLOWANCES	ALLOW	1	\$ 5,000.00	\$ 5,000.00
9	SUBSURFACE UTILITY LOCATION ALLOWANCE	ALLOW	1	\$ 10,000.00	\$ 10,000.00
10	COMMUNITY CENTER IRRIGATION CISTERN CONNECTION LOCATE	ALLOW	1	\$ 10,000.00	\$ 10,000.00
11	SEEDING, NATIVE, CIP	AC	0.57		
12	EROSION CONTROL AND SWPPP, COMPLETE	LS	1		
BASE BID ROADWAY					
13	SAWCUT, REMOVE, AND REPLACE ASPHALT CONCRETE	SQYD	1,214		
14	EXISTING CURB & GUTTER, PC CONCRETE, REMOVE & REPLACE, COMPL.	LF	45		
BASE BID WATER					
15	REMOVE AND REPLACE EXISTING FENCE AND GATE IN-KIND, CIP. SEE SHEET C-202.	LS	1		
16	12" C-900 PVC WATERLINE PIPE, EXCL FITTINGS, INCL TRACE WIRE, TRENCH & COMPACTED BACKFILL, UP TO 6' DEPTH, CIP	LF	2,714		
17	8" C-900 PVC WATERLINE PIPE, EXCL FITTINGS, INCL TRACE WIRE, TRENCH & COMPACTED BACKFILL, UP TO 6' DEPTH, CIP	LF	2,347		
18	6" DI PIPE WATERLINE, EXCL FITTINGS, INCL TRACE WIRE, TRENCH & COMPACTED BACKFILL, UP TO 6' DEPTH, CIP	LF	45		
19	4" C-900 PVC WATERLINE PIPE, EXCL FITTINGS, INCL TRACE WIRE, TRENCH & COMPACTED BACKFILL, UP TO 6' DEPTH, CIP	LF	14		
20	4" GATE VALVE	EA	1		
21	6" GATE VALVE	EA	8		
22	8" GATE VALVE	EA	5		
23	12" GATE VALVE	EA	13		
24	VALVE BOX, TYPE A	EA	19		
25	DUCTILE IRON MJ FITTINGS, ALL SIZES, CLASS 250, INCL JOINING MATERIAL, CIP.	LB	7,824		
26	12" JOINT RESTRAINING HARNESS, DI & PVC	EA	14		
27	8" JOINT RESTRAINING HARNESS, DI & PVC	EA	7		
28	MECHANICAL JOINT RESTRAINING GLAND, DI & PVC, 4"-10", CIP.	EA	51		
29	MECHANICAL JOINT RESTRAINING GLAND, DI & PVC, 12"-16", CIP.	EA	50		
30	NEW SERVICE, INCL. TAPPING SADDLE , CUSTOMER METER, PIPE, AND ALL APPURTENANCES, INCL. ASPHALT REMOVE AND REPLACEMENT, ALL SIZES, CIP.	EA	4		
31	4" FIRE SUPPRESSION SERVICE (SHEET C-204)	LS	1		
32	2" CLINIC SERVICE (SHEET C-204)	LS	1		
33	NON-PRESSURIZED CONNECTION, EXISTING WATER LINE, ALL SIZES, INCL FITTINGS, COMPL.	EA	3		
34	8" MASTER METER INCL VAULT, VALVES, FITTINGS, AND DI	EA	1		
35	WELL SITE DEMOLITION, INCL EVERYTHING ON SHEET C-302	LS	1		
36	NEW IRRIGATION SERVICE TO EXISTING (DETAIL A1 ON SHEET C-301) INCLUDING BACKFLOW PREVENTER	LS	1		
37	8" BACKFLOW PREVENTER	EA	1		
38	FIRE HYDRANT, 4' BURY, COMPLETE IN PLACE	EA	8		
BASE BID ELECTRICAL					
39	POWER SERVICE	LS	1		
40	COMMS	LS	1		

TOTAL:

Total written in words